BRUHAT BANGALORE MAHANAGARA PALIKE
YELAHANKA ZONE, BANGALORE

No: BBMP/EE/BTP/WO/ 272 /2015-16

Executive Engineer,
Byatarayanapura Division,
No. 2152/20, Defence Colony,
Sahakara Nagara,Bangalore-92
Tel:080 22975937

Date: 01/03/2016

WORK ORDER

To,

Sri. B. Shankar,

Huttanahalli village,
chikkajala post,
Bangalore north.

Pursuant to signing of the contract Agreement for the below mentioned work, you are here by instructed to contact AEE (BSD/KSD/VSD) & proceed with the execution of the works in accordance with the contract documents.

Name of Work	**Providing Concrete drains in Agasarahatti, Jakkur Village, Ward No .7, Byatarayanapura**
Est.Cost	25.00 lakhs
Job Code/ Indent No.	007-16-000019 18674
Head of Account	P1771 POW
Administrative Approval No	AS/ EE(BTP)/69 /15-16 Dt:14.12.2015
Technical Sanction No	TS/ SE(BTP)/ 28 /15-16 Dt:14.12.2015
Tender Notification Number	BBMP/EE/BTP/E-PMT/03/2015-16, Date: 22.01.2016
Amount Put to Tender	2485824.00
Approved Tender Price	2345832.06
Percentage	-5.63%
Period of Completion	90 days
Remarks	Difference amount Rs.140000/- DD No.444622, 444623 Dt:19.01.2016 The Karnataka Bank Ltd., 5% FSD Amount Rs. 117300/- DD No0335102 Date:29.02.2016 Indian bank.

Executive Engineer,
Byatarayanapura Division,
BBMP, Bangalore.

B.S.L to AE

01/03

Copy Submitted to

1. The Chief Engineer, Yalahanka Zone for kind information.
2. The Executive Engineer, quality control, BBMP, Bangalore.
3. The Assistant Executive Engineer, Byatarayanapura/Kodigehalli/Vidyaranyapura Sub Division along with Schedule-B for necessary action and with instructions to hand over the site and commence the work forthwith and complete with in the stipulated time.
4. The Assistant Controller of Finance, Yalahanka Zone for information.
5. The Account Superintendent, Byatarayanapura Division along with original file for information.
6. Copy to file.

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT18674/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Providing Concrete drains in Agasarahatti, Jakkur Village, Ward No .7, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B SHANKAR		
				In Figures		In Words
1	570.4	KSRRB 300-47 Scarifying Kankar /gravel/ metal crust upto 150mm thick with power roller and scarifier , disposal of stuff including cost of labour charges HOM of machinaries MORTH Specification No. 305.4.3 (P-146, Item No. 19.53 SR 2015-16)	Sqm	25.0	14260.00	Rupees Twenty Five Only
2	346.16	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 1.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3.	cum	79.0	27346.64	Rupees Seventy Nine Only
3	117.04	KSRB 4-1.3: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P. 12, I.No. 4.3) SR-2015-16	cum	4784.0	559919.36	Rupees Four Thousand Seven Hundred Eighty Four Only
4	138.4	KSRB5 25 providing and constructing non load bearing with cement concreate solid blocks with compresive strenth not less than 3.5 newtown per sqmm with cement mortor 1:4 with block of size 40X20 X20cms (lXbXh) conforming to is:2185/1965 in superstructure including the cost of materials labour charges , scaffolding curing complete as specification (P.No.25 I.No.5.27 of PW,P&IWTD S.R 2015-16	Sqm	961.0	133002.40	Rupees Nine Hundred Sixty One Only
5	570.4	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. (148, I.No. 19.64) 2015-16	cum	4.6	2623.84	Rupees Four and Sixty Paise Only
6	153.04	Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum) (P. 18, I.No. 4.48 SR-2015-16	cum	5974.0	914260.96	Rupees Five Thousand Nine Hundred Seventy Four Only
7	570.4	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift. (P. 174 I. No. 22.7) SR-2015-16	cum	91.7	52305.68	Rupees Ninety One and Seventy Paise Only
8	50	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. for concrete pavement(P. 172 I. No. 22.8.1) SR-2015-16	cum	117.0	5850.00	Rupees One Hundred Seventeen Only

B. Sr Jr Asst.

1/3/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B SHANKAR		
				In Figures		In Words
9	9.3	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P. 17, I.No. 4.46.2) SR-2015-16	Qtl	65862.0	612516.60	Rupees Sixty Five Thousand Eight Hundred Sixty Two Only
10	346.16	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km (Page No.141)	cum	68.6	23746.58	Rupees Sixty Eight and Sixty Paise Only
					2345832.06	

B.S.D.C.L
Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
1/12/16

01/03